GRADE	A=Trees of high quality >40 years life espectancy
	B= Trees of moderate quality >20 years life expectancy
	C= Trees of low quality >10 years life expectancy
	U= Trees of low quality <10 years life expectancy
	1= Mainly arboricultural qualities
	2= Mainly landscape qualities
	3= Mainly cultural qualities including conservation
	U= No value. Remove/Fell
Root protection area	RPA radius=Radius in metres of root protection area as per BS5837:2012

Trees to be removed

Planting Beds to be removed

Trees and Vegetation to be retained

Grass Areas

Japanese Knotweed with potential 7m zone of influence

GORSEINON ROAD

POUNDLAND

Footpath

Low wall frontages

Illuminated Sign for Tyre Works

Rough Grass Verge

Gorseinon Tyre and Service Centre

Mainly Senecio Sunshine, Hebes Prunus Otto Luyken and Dogwood

Prunus Otto Luyken Block

Mainly Senecio Sunshine and Hebes

T8 Sorbus Hgt 4m C2

G4 2no Ash Hgt 9m Inspect in August,early September 2021 for signs of ash dieback.

T7 Sorbus Hgt 4m C2

T2 Birch Hgt 6m UU Fell to ground

T3 Birch Hgt 7m C2 Cut out Deadwood

T4 Birch Hgt 8m C2

T5 Birch Hgt 7m UU Fell to ground

T6 Sorbus Hgt 4m C2

Dogwood Block

Retaining Wall
Bare earth strip
Metal palisade fence

Dogwood Block

Steep Bank

Existing Lidl Store

Palisade Fence ends

Electricity Sub Station

Mixed Planting predominantly native species including trees

Portuguese Laurel Block

Sorbus

Check for Japanese Knotweed on this boundary

Lonicera

Bramble
Buddleia

Japanese Knotweed growing into site in places.

NOTE OFF SITE tree categories T1, G2, G3 are recommendations for felling.
ON SITE Current action cutting back crowns and stems growing through fence

Industrial Unit

Tank

Tank

Tarmac

Concrete

Concrete Service Yard

Greenhouse

Concrete

Tarmac

Timber Yard

Metal Palisade Fence

Area Derelict
Weed Growth
Boundary High Security Mesh Fence with barbed wire top

Dogwood

Gravel

Cotoneaster OFF SITE

Japanese Knotweed

G3 3 No Birch Hgt 8m C2 OFF SITE

Tall High Security Mesh Fence with barbed wire top

T1 Goat Willow 7 Stems Hgt 7m UU Fell to ground or reduce crown growing through fence. OFF SITE

G2 3No Goat Willow Hgt 7m UU Fell to ground level and treat stump OFF SITE

Cotoneaster waterei
Dogwood spp
Gorse OFF SITE

Industrial Unit

G1 3No Goat Willow Hgt 6m UU Fell to ground level and treat stump

ONE WAY

NO PARKING

EXIT

NOTICE

0m 10m 20m

Corscadden Associates
77 Fairleigh Road
Pontcanna, Cardiff. CF11 9JW
Tel 02920 373053

email ca@corscaddenassociates.com

LIDL STORE : GORSEINON

Drawing Title

EXISTING FEATURES &TREE SURVEY

Scale	Date
1:500 at A3	18 Dec 2020
173	**2020 G-01 Rev A**

Drawing No

2020 G-01 Rev A
28 Dec 2020
28 Dec 2020
Additional tree and Knotweed notes